

BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

BBMP/2015-16/OW/WORK_INDENT19394

Executive Engineer

Yelahanka Division

B.B.M.P. Bengaluru - 64

No:EE/YNK-D/E-PMT/01/2015-16 Dated: 04-01-2016

Approved Tender Schedule - B**Item No: 10**

Name of Work :-Providing Kerb painting work and laying missing covering slabs and kerb stones at BB road yelahanka in ward No- 01 of yelahanka Sub division.

Sl	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri R SATHEESH	
				Rate	Amount
1	5.29(b) Providing and fixing pre cast solid cement concrete kerb stones made out of C.C 1:2:4 with top and bottom width 114 and 165mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting, including formwork curing, including, cost of all materials, labour hire charges of machinery, loading unloading, lead and lift, transportation etc, complete. Page No Item No. 25 item no 5.30 / PWD SR 2015-16	Nos	2444.00	333.00	Rupees three hundred thirty three and paise zero only
2	KSRB 15.15.1: Providing and applying painting in two coats with plastic emulsion paint of approved brand on wall surface to give an even approved shade after thoroughly brushing the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth cost of materials, labour, complete as per specifications. 113, item No 15.51 SR 2015-16	Sqm	1620.00	80.00	Rupees eighty and paise zero only
3	RCC Precast covering slab for drain (10cm thick)	Sqm	24.00	1500.00	Rupees one thousand five hundred and paise zero only
4	KSRB 2-2.1 : earth work excavation for foundation of buildings, culverts water supply, sanitary line and electrical conduits either in pits or in trenches 1.5m and above in width, in ordinary soil not exceeding 1.5m, in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50m, after breaking of clods complete as per specifications, specification, No, KBS 2.1(a) / 2.3.5, No. 5/ Item No. 2.3/ PWD SR 2015-16	Cum	31.80	250.00	Rupees two hundred fifty and paise zero only
5	KSRB 100-1 Loading and unloading of stone aggregates / sand/ kanker/ Moorum /soil KSRB M100-1 Placing tipper at loading with front end loader dumping turning for return trip excluding time for hauled and return trip complete as per specification item No 17.1 page 130 and KSRB M.100.4.1 cost of haulage excluding loading and unloading MORTH to a distance of 4.00 K.M (Item No 17.4 Page 130 (SR 2015-16)	Cum	31.80	100.00	Rupees one hundred and paise zero only

	Description of work	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri R SATHEESH	
				Rate	Amount
6	KSRB-4-1.2 : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement at 220kgs, with 40mm and down size graded granite metal coarse aggregates @0.892cum and fine aggregates @0.465cum machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1.4.2, No. 12/ Item No. 4.2/ PWD SR 2015-16	Cum	23.85	5300.00	Rupees five thousand three hundred and paise zero only
7	KSRRB M600-6: cement concrete pavement, construction unreinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with 43 grade cement or any other type as per clause 1051.2.2 with 25mm and down size graded granite metal coarse aggregates and fine aggregates with surperlatisiser @ 3its conforming to IS103-1999 fine, reaffirmed-2008 mixed in a concrete mixed of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design capacity laid in approved fixed side form wedges steel plates including levelling the from work as per drawing) & spreading the concrete and finished roller compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion construction and longitudinal joints including groove cutting charges joint filler separation membrane sealant primer joint sealant admixtures and approved curing compound finishing to lines and grades as per drawing complete as per specification M 30 at 360 kg per cum coarse aggregate @ 0.69cum and fine aggregate @0.49cum	Cum	15.90	6000.00	Rupees six thousand and paise zero only
8	Vacuum De-watering with vacuum pump and suction mat and compaction with skin flater clubbed with floating disc including cost of generator, HOM of machinery Screed Vibratory Power Floaterblade and disc etc. with all lead and lift. Page No 174 Item No 22.7 SR 2015-16	Sqm	159.00	100.00	Rupees one hundred and paise zero only
9	Providing groove cutting for width of 5mm to 100mm depth 80mm-100 including cost of cutting machine, generator & HOM of machinery, including cost of blade, coolant etc., including cleaning of groove & providing sand and hot bitumen fillers, and filler metal etc., including cost of conveyance of all materials, Labour, lead and lift charges and all other incidental charges as per drawing and as per specifications. do- for concrete pavement Item no 22.8.1 Page No 178 SR 2015-16	Rmt	39.00	200.00	Rupees two hundred and paise zero only

Signature of the contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.